# Solar Rooftop Quotation Comparison – Kiran Classic-3 (C Wing), Katargam, Surat

40 Flat × 1.84 kW (Personal) + 1 × 12.3 kW (Common) = 140 Panel | 5 Company ke quotation (Sep–Oct 2026) | Taiyaar: 22-10-2026

## 1. Ek Flat ka Kharcha (Personal ~1.84 kW, 3 Panel)

| | Greeneable Solar (Amroli) | Sunshine Solar (Mota Varachha) | Solixa (Amroli, 63560 09090) | Solar Planet (Jahangirabad) | Devdeep Electricals (Nani Ved) |
|---|---|---|---|---|---|
| Capacity | 1.85 kW | 1.83 kW | 1.845 kW | 1.86 kW | 1.845 kW |
| System ki keemat | ₹1,15,000 | ₹90,875 | ₹87,750 | ₹92,800 | ₹1,07,600 |
| Meter charge | INCLUDED | + ₹5,500 | + ₹5,400 | + ₹5,300 (approx) | + ₹5,317 (Torrent) |
| Structure / Network extra | INCLUDED | + ₹19,000 | + ₹21,000 | + ₹14,000 | + ₹10,900 |
| Stamp / MCB | Likha nahi | Stamp included | + ₹350 stamp | + ₹350 stamp | + ₹500 MCB |
| Kul bill (subsidy se pehle) | **₹1,15,000** | **₹1,15,375** | **₹1,14,500** | **₹1,12,450** | **₹1,24,317** |
| Subsidy (bank me wapas) | – ₹55,500 | – ₹54,900 | – ₹55,350 | – ₹55,800 | – ₹55,500 |
| ASLI KHARCHA / FLAT | **₹59,500** | **₹60,475** | **₹59,150** | **₹56,650 (sabse sasta)** | **₹68,817** |
| Optional | – | – | – | – | Sprinkler ₹2,500, RCCB ₹1,300 |

## 2. Common 12.3 kW (20 Panel) – Society ka kharcha

| | Greeneable Solar | Sunshine Solar | Solixa | Solar Planet | Devdeep Electricals |
|---|---|---|---|---|---|
| Kul bill | ₹6,08,000 | ₹6,12,138 | ₹6,38,000 | Common ka quotation **diya hi nahi** | ₹5,76,000 (structure sahit) |
| Inverter | Deye (size likha nahi) | Deye 10 kW | Deye 12 kW | | 12 kW Solaryaan / V-Sole / Deye |
| Meter (3 phase) | Extra (society bharegi) | Extra (society bharegi) | Extra (society bharegi) | | Torrent ₹20,942 extra (amount bataya) |
| Subsidy | – ₹2,21,400 | – ₹2,21,400 | – ₹2,21,400 | | – ₹2,16,000 |
| ASLI KHARCHA (meter chhod ke) | **₹3,86,600** | **₹3,90,738** | **₹4,16,600** | | **₹3,60,000 (sabse sasta)** |

## 3. Poori Building ka Total (40 Flat + Common, subsidy ke baad)

| Company | 40 Flat | Common | GRAND TOTAL | Sabse saste se kitna zyada |
|---|---|---|---|---|
| **Greeneable Solar** | ₹23,80,000 | ₹3,86,600 | **₹27,66,600** | **– (sabse kam)** |
| Solixa | ₹23,66,000 | ₹4,16,600 | **₹27,82,600** | + ₹16,000 |
| Sunshine Solar | ₹24,19,000 | ₹3,90,738 | **₹28,09,738** | + ₹43,138 |
| Devdeep Electricals | ₹27,52,680 | ₹3,60,000 | **₹31,12,680** | + ₹3,46,080 |
| Solar Planet | ₹22,66,000 | quote nahi | adhoora | Common ke bina compare nahi ho sakta |

* Common meter ka charge (sab me extra; Devdeep ke hisaab se Torrent 3-phase ~₹20,942) upar ke total me nahi hai. Devdeep ke sprinkler optional hain, total me nahi jode.

## 4. Hamari Zaroorat (Spec) – Kisne di, kisne nahi

Haan – mil raha he | Adhoora / likha nahi | Nahi

| Hamari Maang | Greeneable Solar | Sunshine Solar | Solixa | Solar Planet | Devdeep Electricals |
|---|---|---|---|---|---|
| 615W Waaree / Pahal / Goldi panel | Waaree 610-620W TOPCON | Waaree 610-615W | Waaree 615W | 620W Goldi/Waaree/Pahal – brand fix nahi | Waaree 615W TOPCON Bifacial |
| 140 Panel (40×3 + 20) | 3 + 20 | 3 + 20 | 3 + 20 | Common nahi | 3 + 20 |
| Torrent Power meter | Flat meter included; Torrent naam nahi | DGVCL likha, meter extra | DGVCL likha, meter extra | Meter extra; DISCOM naam nahi | Torrent saaf likha (extra charge) |
| Deye 2 kW Inverter | Deye, size likha nahi | Deye 2 kW | Deye 2.7 kW (bada – thik) | V-Sole *ya* Deye | V-Sole/Solaryaan; Deye "stock ho to" |
| Structure 80×40×2mm (Leg & Rafter) | 60×40, motai likhi nahi | 60×40×2mm (80 nahi) | 80×40 Apollo, motai nahi | Size list, motai nahi | 80×40×2mm |
| Purlin 40×40×2mm | 60×40, motai nahi | 40×40×2mm | 40×40, motai nahi | Likha nahi | 40×40×2mm |
| Hot-Dip GI 60 micron | Hot-dip GI, micron nahi | Hot-dip GI 60 micron | Likha nahi | Likha nahi | Hot-dip GI, micron nahi |
| RR / Polycab wire | Polycab | RR / Polycab | Polycab | Polycab | Polycab / RR |
| LA Cable 16 sqmm | 16 sqmm (Kanbery) | 16 sqmm AL | 16 mm (Deluxcab) | Size likha nahi | LA cable size likha nahi |
| Earthing wire 2.5 sqmm | 2.5 sqmm Polycab | "As per requirement" | 2.5 & 6 sqmm Polycab | 4 sqmm + copper rod | 2.5 sqmm Cu Polycab/RR |
| **Score (10 me se pura)** | **5** | **7** | **6** | **2** | **7** |

## 5. Payment aur Shartein

| | Greeneable Solar | Sunshine Solar | Solixa | Solar Planet | Devdeep Electricals |
|---|---|---|---|---|---|
| Advance | 40% advance, 10% meter ke baad | 80% advance (bahut zyada) | 50% advance, 50% dispatch se pehle | 50% / 40% approval / 10% dispatch | ₹10,000 advance, phir verification ke baad **poora** payment kaam se pehle |
| Warranty / Service | Panel 30 saal, Inverter 10 saal | Likha nahi | Likha nahi | Inverter 10 saal onsite | 5 saal system warranty + 5 saal CMC |
| Khaas baat | Walkway, SS-304 tie, zinc-spray welding | 3 earthing kit, SS-304 J-clamp, extra wire included | Sirf 30 m wire, baaki extra | 2 walkway + 2 ladder, copper earthing | MCB/ELCB customer dega; cleaning customer karega |

## 6. Natija – Kisko Contract Dein?

**Budget me sabse acchi deal: GREENEABLE SOLAR** – poori building ka sabse kam kharcha (₹27.67 lakh), flat ka meter & structure included, aur sirf 40% advance.
**Shart:** Contract se pehle likhwa lo – Structure **80×40×2mm** leg/rafter, **40×40×2mm** purlin, **Hot-dip GI 60 micron**, **Deye 2 kW** (common me 10/12 kW), aur **Torrent Power** meter.

**Doosra option: SUNSHINE SOLAR** – spec me sabse accha (Deye 2kW, 60 micron likha), ₹43,000 zyada, lekin **80% advance** kam karwana padega.

**DEVDEEP ELECTRICALS** – structure 80×40×2mm, Torrent meter aur 5 saal CMC sabse acche, common bhi sabse sasta. Lekin har flat ~₹9,300 mehenga (building par ~₹3.5 lakh zyada) aur **Deye pakka nahi** (V-Sole/Solaryaan de sakte hain). Deye likh ke de aur rate kam kare to achha option.

**Dhyan do:**

- Solar Planet ne common 12.3 kW ka quote nahi diya – flat ka rate sabse sasta par spec adhoori.
- Katargam me bijli **Torrent Power** ki he – sirf Devdeep ne Torrent likha; Sunshine/Solixa ne DGVCL. Sabse confirm karwao.
- Structure ka size/motai/micron aur inverter brand "likh ke" lo, warna baad me sasta maal lag sakta he.
- Quotation 6-10 din ke liye valid the (Sep–Oct 2026) – naya rate confirm karo.